

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>42N</u> R <u>32W</u>	<u>69</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S <u>28</u> T <u>42N</u> R <u>32W</u>	<u>7</u>
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jan 20 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. Reestablished in 1971 and recorded by A.O.Enger RLS for the Michigan Dept. of Natural Resources: Set 1"IDx36" I.pipe with 4" aluminum cap. J.Pine 6 S54W 25.4', J.Pine 6 S19E 36.8', Aspen 8 N35W 7.0'. Found no subsequent record.

(7-Sec. 28) North 1/16 corner between Sections 27 and 28. Established in 1971 and recorded by A.O.Enger RLS for the Michigan Dept. of Natural Resources. Set 1"ID x36" I.pipe with 4" aluminum cap. J.Pine 8 S28W 13.1', J.Pine 6 N74W 12.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) Recovered the 1971 monument, in good condition, and at record bearing and distance from the two J.Pine witnesses, now both dead and down. The Aspen NBT was not recovered. Accepted the monument as a careful and faithful reestablishment of the position of the corner and made new witnesses as described below.

(7-Sec. 28) Recovered the 1971 monument in good condition, projecting about 5" above ground and checked its location by approximate measurement to adjacent section and quarter corners. Both of the 1971 BTs have been cut down. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Found 1"ID I.pipe with 4" alum. cap. Blazed, scribed, and set measuring nails in:  
 9" Oak N09W 50.9' "S21 NBT"  
 7" W.Pine N17E 33.4' "S22 NBT"  
 6" W.Pine S55E 24.2' "S27 NBT"  
 24" R.Pine S15W 51.6' "S28 NBT"  
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(7) Found 1"ID I.pipe with 4" alum. cap. Blazed, scribed, and set measuring nails in:  
 7" R.Pine N23W 39.1' "1/16S BT"  
 5" R.Pine N60E 13.3' do  
 5" R.Pine S11E 33.4' do  
 12" R.Pine N87W 28.9' do  
 Bearings are magnetic. Distances are to nail with tag. Sq'd an 8" R.Pine S25W 3.5' distant for a post.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/9/04

For the Michigan Department of Natural Resources, Office of Land and Facilities

