

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>32W</u>	<u>G10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>42N</u> R <u>32W</u>	<u>16</u>
	S <u>28</u> T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

16 Jan 15 2004
 G10 Jan 14 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27 and 28. Remonumented in 1971 and recorded by A.O. Enger RLS for the Michigan Dept. of Natural Resources. 1"IDx36" iron pipe with 4" aluminum cap. J.Pine 6 N52W 10.8', J.Pine 5 S40W 8.1'.
 (16-Sec. 28) East 1/16 corner between Sections 28 and 33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 witnesses. The J.Pine S40W is standing dead with scribing visible. The J.Pine NW is in good condition with scribing visible.
 (16-Sec. 28) Established the corner midway and on a line of mean true bearing between Quarter corner 1318.10' West and Section corner 1318.10' East. From the position thus established, I found a 1"ID iron pipe, projecting 9" above ground, not of record, 11.2' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Found 1"ID I.pipe with 4" alum. cap. Blazed, scribed, and set measuring nails in:	(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
7" J.Pine N47W 11.1' "1/4S NBT" *	8" Aspen N51E 12.7' "1/16S BT"
4" Oak S21E 31.2' do	5" W.Pine S59E 79.5' do
8" R.Pine S35W 27.2' do	18" R.Pine S81W 97.8' do
5" R.Pine S87W 30.6' do	12" W.Pine N29W 61.9' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1971 NBT.	Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/9/04

For the Michigan Department of Natural Resources, Office of Land and Facilities