

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 42N R 32W	G11
	T 42N R 32W	F11
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

F11 Jan 13 2004  
 G11 Dec 30 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G11) Corner common to Sections 27-28-33-34. Remonumented in 1971 and recorded by A.O.Enger RLS for the Michigan Dept. of Natural Resources. 1"IDx36" iron pipe with 4" aluminum cap. Aspen 10 S70E 95.6', Aspen 7 N26E 49.1'.

(F11) Quarter corner common to Sections 28 and 33. 1849: Established by L.B. Searles, Deputy Surveyor: West Corrected [between Sections 28 and 33]...40.00 Set Hemlock qr section post. Hemlock 20 S31W 27, Hemlock 10 N14E 23...80.00 Section corner. 1962-1982 MDOT plans for CS 36051 show 3/4" iron pipe with witnesses 4" S.Pine S60E 22.15', 24" S.Pine S80W 17.72', 19" S.Pine North 35.00', Distance east to G11 shown as 2693.04'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G11) Recovered the 1971 monument in good condition, at record bearing and distance from the remaining witness 8" Aspen N23E 49.5' found with no markings. The position of the Aspen S70E is now in a clearcut and the NBT was not recovered. Found a 1.25" ID iron pipe, projecting 3.5' above ground, adjacent to the monument. Accepted the monument as a perpetuation of the position of the original corner. Left the monument in place and made new witnesses.

(F11) The original post and accessories were not recovered. Found a 1" dia. iron pipe, projecting 25" above ground, in accord with MDOT record, 2692.91' west of G11 as recorded. The mile between Sections 28 and 33 measures 5272.40' (GLO 5280). The found pipe is unreasonably far distant (56.7' west and 9.8' south) from the record position and I do not accept it as marking the position of the original corner. I reestablished the corner midway and on a line of mean true bearing between monumented section corners 2636.20' east and west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G11) Found 1"ID Iron pipe with 4" alum. cap. Blazed, scribed, and set measuring nails in:

8" Aspen N23E 49.9' "S27 NBT"  
 4" Aspen S78E 36.2' "S34 NBT"  
 6" Cherry S18W 46.0' "S33 NBT"  
 4" Aspen N49W 54.5' "S28 NBT"

Bearings are magnetic. Distances are to nail with tag.

(F11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:

18" R.Pine N55E 35.8' "1/4S NBT"  
 12" Maple S44E 30.1' do  
 14" W.Pine S46W 32.1' do  
 14" W.Pine N63W 23.2' do

Bearings are magnetic. Distances are to nail with tag. Placed a cedar post adjacent.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/9/04

For the Michigan Department of Natural Resources, Office of Land and Facilities