

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 42N R 32W	F9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 33 T 42N R 32W	6
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

6 Jan 22 2004  
 F9 Jan 20 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(F9) Quarter corner common to Sections 21 and 28. Reestablished in 1971 and recorded by A.O.Enger, RLS for the Michigan Dept. of Natural Resources: Set 1"IDx36" I.pipe with 4" aluminum cap. Red Oak 8 N10W 15.7', Red Oak 10 S70W 6.3'.  
 (6-Sec. 33) Northeast 1/16 corner, Section 33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F9) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 witnesses, both in good condition. Verified the position of the monument by measurement to adjacent section corners. Accepted the monument as a careful and faithful reestablishment of the position of the corner. Left the monument in place and made two new witnesses.  
 (6-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F9) Found 1"ID I.pipe with 4" alum. cap. Blazed, scribed, and set measuring nails in:	(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
13" Oak S78W 7.0' old blazes *	7" Maple N19E 12.4' "1/16S 8T"
11" Oak N04W 15.8' do *	7" Oak S6E 28.65' do
4" R.Pine N81E 20.8' "1/4S NBT"	8" R.Pine S71W 38.6' do
7" Oak S41E 27.0' do	7" W.Pine N65W 36.1' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1971 NBT.	Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/9/04