

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>42N</u> R <u>32W</u>	<u>D10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>29</u> T <u>42N</u> R <u>32W</u>	<u>2</u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 29 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (D10) Center of Section 29. Not established in the original survey.

(2-Sec. 29) East 1/16 corner between Sections 20-29. Established in 1972 by A.O. Enger RLS midway and on line between reestablished Quarter and Section corners. Set 1"IDx36" Iron pipe with 4" aluminum cap. Red Maple 4 N66W 26.5', W. Birch 5 N70E 39.7'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(D10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(2-Sec. 29) Recovered the 1972 monument in good condition, at record bearing and distance from the R. Maple NBT, 0.12' South and 0.67' West of the record position between the reestablished corners. Accepted corner position as found.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(D10) Set 1"IDx32" I. pipe with 4" alum.

MDNR cap. Blazed, scribed, and set

measuring nails in:

13" Oak N08E 19.7' "C1/4 BT"

10" Maple N88E 8.3' do

6" Maple S22W 25.7' do

5" Maple N52W 9.5' do

Set sq'd cedar post adjacent. Bearings

are magnetic. Distances are to nail

with tag.

(2) Found 1"ID I. pipe with 4" alum. MI

Dept. of Conservation cap. Blazed,

scribed, and set measuring nails in:

11" Maple N65W 26.5' overgrown blazes

7" Oak S71E 51.1' "1/16S BT"

3" Oak S10E 23.5' do

4" Maple S31W 17.2' do

Set sq'd cedar post adjacent. Bearings

are magnetic. Distances are to nail

with tag.



Signed by Stephan J. Szyszkoski

Date 8/6/03

Surveyor's Michigan License No. 33986