

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>42N</u> R <u>32W</u>	<u>63</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>2</u>	
	S <u>10</u> T <u>42N</u> R <u>32W</u>	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3							●	●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Mar 09 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(63) Corner common to Sections 3-4-9-10. 1953: Reestablished by Murray Gates RLS 2280, "5219' South and 5266' West of established corners in accordance with Gov't notes". Set Wis. Mich. Power Co. pipe marker. New witnesses: 10" J. Pine N45E 59.3', 5" J. Pine S30E 62.8', 3" J. Pine S25W 75.4'. (rec. L.2 P.22 L.C.R.). 1971: The 1953 monument was recovered and accepted by A.O.Enger RLS who made the following new witnesses: J. Pine 6" N39E 12.1', J. Pine 5" S48E 17.7'.  
 (2-Sec. 10) East 1/16 corner between Sections 3 and 10. Not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(63) Found and accepted a 2" dia. WMPCO pipe monument with 3 1/4" dia. brass cap, appropriately stamped to identify the corner, in good condition, projecting about 19", and at record bearing and distance from the 1971 witnesses (the J. Pine SE is standing dead, the J. Pine NE is in good condition). Left the monument in place and made new witnesses as described below.  
 (2-Sec. 10) Recovered a WI-MI Power Company pipe monument capped with a brass cap, appropriately stamped, 1.77' North and 0.12' West of the proportionate position between Section and Quarter corners of record. Accepted same as a careful and faithful determination of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(63) Found WMPCO pipe monument with brass cap. Set measuring nails in:	(2) Fd. WMPCO pipe monument with 3.25" dia. brass cap. Set measuring nails in:
12" J. Pine N42E 12.5' old blazes *	7" R. Pine S77W 9.8' mrkd "1/16S BT"
10" J. Pine S20E 39.6' mrkd "S10 NBT"	7" R. Pine N31W 27.5' do
6" J. Pine S44W 54.7' "S9 NBT"	7" R. Pine N09W 31.1' do
6" J. Pine N28W 14.7' "S4 NBT"	5" Poplar S24E 19.2' do
Set sq'd J. Pine post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1971 NBT.	Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/27/06