

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>32W</u>	<u>G5</u>
	T <u>42N</u> R <u>32W</u>	<u>H5</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●	●					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Mar 16 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G5) Corner common to Sections 9-10-15-16. 1971: A.O. Enger RLS found and accepted a 2" IDx55" iron pipe set by persons unknown. He replaced the pipe with a 1" IDx36" I. pipe with 4" alum. MI Dept. of Conservation cap. No witnesses were taken. Corner recorded in Liber 1 of L.C.R. Pages 217-218, Iron County Records.

(H5) Quarter corner common to Sections 10 and 15. 1991: Reestablished by Edward Kazianka RLS at the midpoint and on line between previously recorded Section corners. Set 4" Aluminum cap on a 1" Iron pipe, four feet long. Jack Pine 6 N06W 9.30', Jack Pine 7 S78W 19.35', 1.25" iron pipe N23W 42.30'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G5) Found the 1971 monument in good condition. Verified the position of the monument by measurement to the Quarter and Section corners to the North and East, both Quarter corners having been reestablished by proportionate measurement to G5.

(H5) The 1991 monument, a 1" ID iron pipe capped with a 4" dia. Kimberly-Clark Corp. cap, appropriately stamped, was recovered in good condition and at record bearing and distance from the witnesses of record. Verified the position of the corner with respect to adjacent Section corners and accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G5) Found 1" ID I. pipe with 4" alum. MI Dept of Conservation cap. Set measuring nails in:

- 5" J. Pine S39E 13.9' mrkd "S15 NBT"
- 6" J. Pine S53W 6.8' "S16 NBT"
- 6" J. Pine N74W 8.6' "S9 NBT"
- 7" J. Pine N08W 10.4' "S9 NBT"

Found 2" I. pipe and 4' tall metal fence post adjacent. Bearings are magnetic. Distances are to nail with tag.

(H5) Found 1" ID I. pipe with 4" alum. Kimberly-Clark cap. Set measuring nails in:

- 7" J. Pine S81W 19.35' old blazes *
- 7" J. Pine N05W 9.35' old blazes *
- 6" R. Pine N12E 29.8 mrkd "1/4S NBT"
- 4" B. Spruce S32E 76.5' do

N20W 42.3' Fd. 1.25" ID I. pipe *
 Bearings are magnetic. Distances to trees are to nail with tag. * denotes 1991 witness.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/06