

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
	S _____ T _____ R _____	_____	
2. Property Controlling in Section	S <u>26</u> T <u>42N</u> R <u>32W</u>	<u>1/64 W. of J9</u>	
	S <u>26</u> T <u>42N</u> R <u>32W</u>	<u>C-E-NW 1/64</u>	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Mar 22 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-E-NW 1/64) The SE corner of the SW1/4 of the NE1/4 of the NW1/4 of Section 26. Not established in the original survey.
 (1/64 W. of J9) E-W 1/64 corner between Sections 23 and 26. Being the NE corner of the NW 1/4 of the NE1/4 of the NW1/4 of Section 26. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-E-NW 1/64) Established the corner midway and on a straight line between 1/16 corner #4 660.88' west and 1/16 corner #5 (unmonumented) 660.88' east.
 (1/64 W. of J9) Established the corner on the Section line between Sections 23 and 26 661.00' east of 1/16 corner #1 and 661.00' west of 1/4 corner J9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-E-NW 1/64) Set 1"IDx32" I.pipe with 4" alum MDNR cap. Set measuring nails in:	(1/64 W. of J9) Set 1"ID x 32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" R.Pine N51E 99.5' mrkd "1/64S BT"	6" R.Pine N21E 27.7' mrkd "1/64S BT"
13" R.Pine N77E 132.1' do	7" R.Pine S80E 35.3' do
4" R.Pine N32W 57.3' do	10" R.Pine N38W 30.4' do
Power pole "N60 300" N21W 108.9'	9" R.Pine N04W 22.7' do
Bearings are magnetic. Distances are to nail with MDNR tag.	Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/19/07

For the Michigan Department of Natural Resources, Office of Land and Facilities