

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S <u>26</u> T <u>42N</u> R <u>32W</u>	<u>1</u>	
	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Mar 27 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 26) West 1/16 corner between Sections 23 and 26. 1972 - Established by A.O.Enger RLS on line between section corner 1321.25' west and quarter corner 1321.25' east. Set 1"IDx36" I.pipe with 4" alum. MDNR cap. J.Pine 12" S43W 55.8', J.Pine 6" S77E 53.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 26) Found the 1972 monument in good condition, substantially at the midway position of record, and at record bearing and distance from the 1972 witnesses, now both dead. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 4" Oak S39E 77.1' mrkd "1/16S BT"
 6" Oak S07E 94.3' do
 5" Oak S23W 73.5' do
 3" Oak S64W 82.1' do
 Metal fence post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/19/07

For the Michigan Department of Natural Resources, Office of Land and Facilities