

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
	S _____ T _____ R _____	_____	
2. Property Controlling in Section	S <u>26</u> T <u>42N</u> R <u>32W</u>	<u>4</u>	
	S <u>26</u> T <u>42N</u> R <u>32W</u>	<u>2</u>	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

2 Mar 27 2007
 4 Mar 22 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 26) Northwest 1/16 corner, Section 26. Not established in the original survey.
 (2-Sec. 26) East 1/16 corner between Sections 23 and 26. 1972 - Established midway and on line between 1/4 and Sec. corners 20.019 ch. west and east, by A.O. Enger RLS. Set 1" IDx36" I.pipe with 4" aluminum cap. J.Pine 5" N52W 15.9', J.Pine 4" S52E 6.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 26) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (2) Recovered the 1972 monument at record distance east of 1/4 corner J9. The monument was found bent over to the north and with a broken aluminum cap in place. The 1972 witnesses were not recovered. The corner falls in a clearcut. Straightened the monument to its apparent original position and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:	(2) Found 1" ID I.pipe with broken 4" alum. MDNR cap. Set measuring nails in:
3" J.Pine N71E 4.8' mrkd "1/16S BT"	9" R.Pine N57E 68.8' mrkd "1/16 BT"
3" J.Pine S18W 22.7' do	6" R.Pine N86E 65.9' do
3" J.Pine S50W 8.3' do	9" R.Pine S48E 64.2' do
3" J.Pine N06W 14.1' do	13" R.Pine S15E 82.4' do
Bearings are magnetic. Distances are to nail with MDNR tag.	Sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/19/07

For the Michigan Department of Natural Resources, Office of Land and Facilities