

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S <u>10</u> T <u>42N</u> R <u>32W</u>	<u>7</u>	
	S <u>11</u> T <u>42N</u> R <u>32W</u>	<u>8</u>	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jun 01 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (7-Sec.10) North 1/16 corner between Sections 10 and 11. Not established in the original survey. Found no subsequent record.
- (8-Sec. 11) West 1/16 corner, Sec. 11. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (7-Sec. 10) Established the corner midway and on line between Section corner 1315.81' North and Quarter corner 1315.81' South.
- (8-Sec. 11) Established the corner midway and on a straight line between Quarter corner 1319.41' West and Center of Section 1319.41' East. From the position thus established, I found a NI-MI brass capped pipe monument S33W 4.2' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (7) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>9" R.Pine N52E 4.9'    mrd "1/16S BT"<br>10" R.Pine N31W 14.1'    do<br>9" R.Pine S34W 14.9'    do<br>8" R.Pine S68E 16.2'    do<br>Set sq'd J.Pine post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag. | (8) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>6" Poplar N55E 8.9'    mrd "1/16S BT"<br>7" Poplar S12E 22.8'    do<br>6" J.Pine S02W 63.5'    do<br>12" J.Pine N43W 52.4'    do<br>Set sq'd cedar post adjacent. Bearings<br>are magnetic. Distances are to nail with<br>tag. |
|---|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/27/06

For the Michigan Department of Natural Resources, Office of Land and Facilities