| LAND CORNER RECORDATION CERTIFICATE  |  |   |
|--|--|---|
| Filing Re  | equirement of Act 74, Mich. P.A. 1970 as   | : Amended   |
| Iron Located In  | Compar Code #  |   |
| (County) Located In  | : Comer Code #   |   |
| 1. Public Land Survey T TT   | R  |   |
| S  |  | Register of Deeds Stamp & File<br>Number          |
|  |  | ABCDEFGHIJKLM                                     |
| 4. Lot No, Recorded Plat<br>5. Private Claims  |  | 2├─ <b>┊</b> ─┼─ <b>┊</b> ─┼─ <b>┊</b> ─┼─┆─┼─┆─┼ |
| 3. Firete stamp  | Mar 22 2007  | 3   |
| Stephan J. Szyszkoski in a field su  | rvey on, 20 do hereby state  | 4 - 7 - 8 - 9 - 10 - 11 - 12 - 12                 |
| that under requirements of P.A. 74. Michigan P.A. of   | 1970, the corner points mentioned in lines 1 and 2   | 5   |
| above were in conformance with regulations and ru<br>survey instructions of the United States Department               | les therefore as required in the current manual of   | 6 18 17 18 15 1                                   |
| decree of a Court of Law and /or that the corner of  | oints mentioned in lines 3, 4 and 5 above were in  | 8 19 20 21 22 23 24                               |
| conformance with the rules of the Michigan Board of established, re-established, monumented, recovered                 | f Land Surveyors or by a Decree of a Court of Law;   |   |
|  |  | 10 30 29 28 27 26 25                              |
|  | same town and range, may be recorded   | 11          |
| on this certificate.   |  | 12 31 32 33 34 35 36                              |
| A. Description of original monument and acco   | essories and/or subsequent restoration:  | 13  |
| (8-Sec. 26) West 1/16 corner, Section 26. Not (11-Sec. 26) Southwest 1/16 corner, Section 26                           | established in the original survey.  Not established in the original survey.   |   |
|  |  |   |
|  |  |   |
|  | <b></b>  |   |
|  | A second of the  |   |
| B. Description of corner evidence found and  | or method applied in restoring or reestablish  | ing corner:                                       |
| (8-Sec. 26) Established the corner midway and Section 26 1321.52' east. (11-Sec. 26) Established the corner at the int |  |   |
| (II-58C. 26) Established the collect at the Inc  | 0130002011 07 007 025 10 25 10 10 10 10 10 10 10 10 10 10 10 10 10   | ·   |
|  | •  |   |
|  |  |   |
|  | and the second s |   |
|  |  |   |
|  | Control of the Contro |   |
| C. Description of monument for corner and a (8) Set 1"IDx32" I.pipe with 4" alum.  MDNR cap. Set measuring nails in:   | (11) Set 1"IDx32" Lapipe with 4 alum.  MDNR cap. Set measuring nails in:   | the position of the corner:                       |
| 7" Poplar N88W 50.1' mrkd "1/16S BT"   | 7" R.Pine North 52.3' mrkd: "1/168 BT"   | 61  |
| 7" Poplar N72W 32.6' do  | 15" R.Pine N84E 16.9' do<br>14" R.Pine S44E 20.2' do   | * STEPHAN J. * SZYSZKOSKI                         |
| 3" Poplar N56W 39.7' do Distances above are to nail/MDNR tag.  | 17" R.Pine S14E 8.6' do  | * EAND *  |
| Buried cable sign N64W 36.7'   | Bearings are magnetic. Distances are to  | SEIRVEYOR   |
| Bearings are magnetic.   | nail with MDNR tag.  | No. 19  |
|  |  |   |
|  |  | ABO   |
| #111   | lat.   | Parts 4/19/07                                     |
| Signed by Signed by  | 22000  | Date  |
| Surveyor's Michigan License No.  | 33986  |   |