

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S 26 T 42N R 32W	12	
	S 26 T 42N R 32W	9	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File
Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Mar 22 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- (12-Sec. 26) South 1/16 corner, Section 26. Not established in the original survey.
- (9-Sec. 26) East 1/16 corner, Section 26. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 26) Established the corner midway and on a straight line between 1/4 corner 1321.83' south and the intersection of 1/4 lines of Section 26 1321.83' north.
- (9-Sec. 26) Established the corner midway and on a straight line between 1/4 corner 1320.28' east and the intersection of 1/4 lines of Section 26 1320.28' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (12) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
10" R.Pine N65E 81.8' mrkd "1/16S BT"
9" R.Pine S48E 107.2' do
14" R.Pine S80E 58.5' do
8" R.Pine N80W 53.2' do
Bearings are magnetic. Distances are to
nail with MDNR tag. | (9) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
4" J.Pine N29E 10.0' mrkd "1/16S BT"
3" J.Pine N68E 9.4' do
3" J.Pine S60E 5.6' do
3" J.Pine N73W 6.8' do
Bearings are magnetic. Distances are to
nail with MDNR tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/19/07

For the Michigan Department of Natural Resources, Office of Land and Facilities