

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| <u>Iron</u><br>(County)               | Located In:             | Corner Code # |
| 1. Public Land Survey                 | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling in Section    | S 25 T 42N R 32W        | 9             |
|                                       | S 25 T 42N R 32W        | 8             |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims                     |                         |               |

Register of Deeds Stamp & File Number

|    | A  | B | C | D  | E | F | G  | H | I | J  | K | L | M  |    |
|----|----|---|---|----|---|---|----|---|---|----|---|---|----|----|
| 1  |    |   |   |    |   |   |    |   |   |    |   |   |    |    |
| 2  | 6  |   |   | 5  |   |   | 4  |   |   | 3  |   |   | 2  | 1  |
| 3  |    |   |   |    |   |   |    |   |   |    |   |   |    |    |
| 4  | 7  |   |   | 8  |   |   | 9  |   |   | 10 |   |   | 11 | 12 |
| 5  |    |   |   |    |   |   |    |   |   |    |   |   |    |    |
| 6  | 18 |   |   | 17 |   |   | 16 |   |   | 15 |   |   | 14 | 13 |
| 7  |    |   |   |    |   |   |    |   |   |    |   |   |    |    |
| 8  | 19 |   |   | 20 |   |   | 21 |   |   | 22 |   |   | 23 | 24 |
| 9  |    |   |   |    |   |   |    |   |   |    |   |   |    |    |
| 10 | 30 |   |   | 29 |   |   | 28 |   |   | 27 |   |   | 26 | 25 |
| 11 |    |   |   |    |   |   |    |   |   |    |   |   |    |    |
| 12 | 31 |   |   | 32 |   |   | 33 |   |   | 34 |   |   | 35 | 36 |
| 13 |    |   |   |    |   |   |    |   |   |    |   |   |    |    |

I, Stephan J. Szyszkoski, in a field survey on 8 04/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 25) East 1/16 corner, Section 25. Not established in the original survey.

(8-Sec. 25) West 1/16 corner, Section 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 25) Established the corner midway and on a straight line between Center of Section 1311.89' west and Quarter corner 1311.89' east.

(8-Sec. 25) Established the corner midway and on a straight line between Center of Section 1317.92' east and Quarter corner 1317.92' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 6" Spruce N24E 36.4' mrkd "1/16S BT"  
 7" twin Maple S52E 28.7' do  
 5" Maple S02W 10.3' do  
 9" Spruce S19W 21.1' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 6" triple W.Ash S86E 27.3' mrkd "1/16S BT"  
 7" Spruce S45W 37.1' do  
 6" Spruce S70W 31.4' do  
 4" W.Ash N37W 32.2' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 06/03/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities