

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>42N</u> R <u>32W</u>	<u>9</u>
	S <u>24</u> T <u>42N</u> R <u>32W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 04/27/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 24) East 1/16 corner, Section 24. Not established in the original survey.

(1-Sec. 24) West 1/16 corner between Sections 13 and 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 24) Established the corner midway and on a straight line between Quarter corner 1315.58' east and Center of Section 1315.58' west. From the position thus established I found a Wisconsin Michigan Power Company capped iron pipe S51W 5.4' distant, which I did not accept as marking the position for the corner.

(1-Sec. 24) Established the corner midway and on the Section line between Section corner 1316.42' west and Quarter corner 1316.42' east. From the position thus established I found a Wisconsin Michigan Power Company capped iron pipe, disturbed, N89W 3.0' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Spruce N35E 25.5' mrkd "1/16S BT"
 10" Sugar S63E 15.2' do
 8" Y.Birch S14W 36.8' do
 11" Ash N81W 42.0' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Maple N65E 23.6' mrkd "1/16S BT"
 8" Maple S07W 22.7' do
 8" Maple S57W 25.35' do
 4" Spruce N66W 14.75' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/03/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities