

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 24 T 42N R 32W _____	10
	S 24 T 42N R 32W _____	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 10 04/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- (10-Sec. 24) South 1/16 corner between Sections 23 and 24. Not established in the original survey.
 - (11-Sec. 24) Southwest 1/16 corner, Section 24. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (10-Sec. 24) Established the corner midway and on the Section line between Section corner 1323.72' south and Quarter corner 1323.72' north.
 - (11-Sec. 24) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- (10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 - 3" Spruce N39E 11.9' mrkd "1/16S BT"
 - 4" Spruce S82E 14.85' do
 - 6" Spruce S14E 22.1' do
 - 5" Balsam S50W 14.35' do
 Set sq'd Balsam post adjacent. Bearings are magnetic.
 - (11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 - 14" Ash N13E 6.2' mrkd "1/16S BT"
 - 10" Ash S18E 21.3' do
 - 11" Ash S34W 22.0' do
 - 12" R.Maple N73W 19.5' do
 Set sq'd Spruce post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 06/03/2009
 Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources, Office of Land and Facilities

