LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #	
(County)			**
1. Public Land Survey	TR TR		
2. Property Controlling in Section	S 24 T 42N R 32W S 24 T 42N R 32W S T R	12 14	
3. Miscellaneous Property in Sec.	S T R R		Register of Deeds Stamp & File Number
4. Lot No. , Re 5. Private Claims	corded Plat12 04/0	09/2009	A B C D E F G H I J K L M 2 6 5 4 3 2 1
above were in conformance with instructions of the United States a Court of Law and /or that the	74, Michigan P.A. of 1970, the corner regulations and rules therefore as require Department of the Interior, Bureau of Lacorner points mentioned in lines 3, 4 and d of Land Surveyors or by a Decree	ed in the current manual of survey and Management or by a decree o I 5 above were in conformance with	y 5 of 6 18 17 16 15 14 13 h 7
NOTE: Not more than 2 corr on this certificate.	ners, all in the same town and range,	, may be recorded	11 12 -31 - 32 - 33 - 34 - 35 - 36 - 31
A. Description of original monument and accessories and/or subsequent restoration:			

(14-Sec. 24) South 1/16 corner between Section 24 T42N-R32W and Section 19 T42N-R31W. Not established in the original survey.

(12-Sec. 24) South 1/16 corner, Section 24. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (12-Sec. 24) Established the corner midway and on a straight line between Center of Section 1319.63' north and Quarter corner 1319.63' south.
- (14-Sec. 24) Established the corner midway and on the Range line between Section corner 1321.18' south and Quarter corner 1321.18' north. From the position thus established I found a Wisconsin Michigan Power Company capped iron pipe N87W 13.7' distant, which I did not accept as marking the position for the corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. (12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: Set measuring nail with MDNR tag in the side of: 6" B.Spruce N83E 9.0' mrkd "1/16S BT" 5" Spruce N32W 32.6' mrkd "1/16S BT" 9" B.Spruce S12W 19.8' do do 4" Spruce N67E 21.4' 5" B.Spruce \$69W 9.7' do 3" Spruce S23E 32.9' do 5" B.Spruce N27W 23.5' 3" Spruce S41W 30.2' do Set sq'd Cedar post adjacent. Bearings are magnetic. Bearings are magnetic.

33986

Date

06/03/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

16221 16230 FORM APPROVED BY MICHIGAN STATE BOARD

14, 1975 CANDS sed Jan., 1983 Rervised Oct., 1995

TEPHAN J

ZYSZKOSK LAND

SURVEYOR

No.