

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 24 T 42N R 32W	8
	S 24 T 42N R 32W	L8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 8 04/27/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 24) West 1/16 corner, Section 24. Not established in the original survey.

(L8) Center of Section 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 24) Established the corner midway and on a straight line between Quarter corner 1315.98' west and Center of Section 1315.98' east. From the position thus established I found a Wisconsin Michigan Power Company capped iron pipe S55W 18.8' distant, which I did not accept as marking the position for the corner.

(L8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. From the position thus established I found a Wisconsin Michigan Power Company capped iron pipe S32W 9.5' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 12" Maple N33E 15.15' mrkd "1/16S BT"
 9" Y.Birch S13E 27.2' do
 9" Maple S41W 11.8' do
 11" Maple N48W 8.0' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(L8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 14" Maple N29E 22.4' mrkd "C1/4 BT"
 9" Maple S80E 14.55' do
 12" Maple S70W 8.0' do
 14" Oak N29W 25.2' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/03/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities