

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 25 T 42N R 32W	3
	S 25 T 42N R 32W	10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10 04/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 25) North 1/16 corner between Sections 25 and 26. 1972 - Established by A.O.Enger RLS midway and on the Section line between Section and Quarter corner, 20.115 chains north and south. Set 1"IDx36" I.pipe with 4" aluminum cap. W.Pine 8" N58W 29.0', R.Maple 5" N47E 20.6'.

(10-Sec. 25) South 1/16 corner between Sections 25 and 26. 1972 - Established by A.O.Enger RLS midway and on the Section line between Quarter and Section corners 20.062 chains north and south. J.Pine 11" N38W 31.2', J.Pine 7" S11E 50.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 25) Found the 1972 monument in good condition and at record bearing and distance from the 1972 bearing trees. The Maple is in good condition, the W.Pine is a dead standing stub. Accepted the monument as a careful and faithful establishment of the position of the corner.

(10-Sec. 25) Found the 1972 monument in good condition and at record bearing and distance from the 1972 bearing trees. The J.Pine SE is in good condition, the J.Pine NW is a rotted stump. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 7" Maple N51E 20.7' old blazes (1972 BT)
 6" Maple S45E 13.0' mrkd "1/16S BT"
 8" Maple N88W 37.25' do
 6" Maple N23E 9.5' do
 Bearings are magnetic.

(10) Fd. 1"ID I.pipe w/ 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 11" J.Pine S07E 50.7' old marks 1972 BT
 7" J.Pine S83W 28.6' mrkd "1/16S BT"
 4" W.Pine N30W 33.85' do
 7" Maple N55E 52.2' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/03/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities