

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 42 <del>XX</del> R. 32 <del>XX</del>	E 2
2. PROPERTY CONTROLLING IN SECTION 4	T 42 <del>XX</del> R. 32 <del>XX</del>	#10 and #15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. . . . . RECORDED PLAT		
5. PRIVATE CLAIMS . . . . .		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER \_\_\_\_\_

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19\_\_ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19\_\_ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E2: Yellow pine post (not found)**  
**Spruce pine 10 S85W 4 (not found)**  
**Yellow pine 10 N55E 16 " "**  
**No subsequent monuments found.**

**Corners 10 and 15: Not established in original survey nor subsequently apparently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E 2: Re-established June 28, 1971 proportionately on line between section corner 39.977 ch. S and section corner 39.076 ch. N.**

**Corner 10: Established August 23, 1971 on line between section corner 19.988 ch. S and 1/4 corner 19.988 ch. N.**

**Corner 15: Established August 30, 1971 on line between section corner 19.948 ch. W and 1/4 cor. 19.948 ch. E.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**  
**Witnesses for Corner E 2: None. No trees large enough in vicinity.**

**Witnesses for Corner 10: Red Oak 6 N73°W (mag.) 8.9 ft. "1/16S, BT"**  
**Red Oak 6 N10°W (mag.) 52.2 ft. "1/16S, BT"**  
**Variation 0°50' East at this corner.**

**Witnesses for Corner 15: J. Pine 5 N27°E (mag.) 4.8 ft. "1/16S, BT"**  
**J. Pine 4 S82°W (mag.) 36.7 ft. "1/16S, BT"**  
**Variation 1°00' East at this corner.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 27, 1972**

**Arthur O. Enger**  
MICHIGAN REGISTERED LAND SURVEYOR  
**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**