

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	I 42 <sup>N</sup> <del>XX</del> R 32 <sup>XX</sup> W.	I 10
2. PROPERTY CONTROLLING IN SECTION 26	I 42 <sup>N</sup> <del>XX</del> R 32 <sup>XX</sup> W.	#3 & #10
3. MISCELLANEOUS PROPERTY IN SECTION	I. <sup>N</sup> <del>XX</del> R. <sup>XX</sup> W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER \_\_\_\_\_

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3 and 5 above were, in a field survey on 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I 10: Maple post (not found)**  
 Y. Pine 24 S40W 55 " "  
 Y. Pine 20 N59E 30 " "  
**No subsequent monuments found.**

**Corners 3 and 10: Not established in original survey nor subsequently, apparently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I 10: Re-established June 25, 1971 on line between section corners 40.101 chains to N and to S.**

**Corner 3: Established June 25, 1971 on line between section corner 20.051 ch. N and 1/4 corner 20.051 ch. S.**

**Corner 10: Established May 8, 1972 on line between 1/4 corner 20.051 ch. N and section corner 20.051 ch. S.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

**Witnesses for Corner I10: Red Maple 4 N66°W 7.1 ft. "1/4S, NBT"**  
**(Variation 1°20' West) Aspen 6 S67°W (mag.) 15.0 ft. "1/4S, NBT"**

**Witnesses for Corner 3: J. Pine 3 N13°W (mag.) 58.2 ft. "BT"**  
**(Variation 1°00' West) J. Pine 3 S11°E (mag.) 83.9 ft. "BT"**

**Witnesses for Corner 10: Cedar 5 S58°W (mag.) 33.0 ft. "1/16S, BT"**  
**(Variation 0°50' West) W. Spruce 12 N30°W (mag.) 24.8 ft. "1/16S, BT"**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 27, 1972**

**Arthur O. Enger**

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**