

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 K. W.	E6
2. PROPERTY CONTROL- ING IN SECTION- 16	T. 42 N. R. 32 K. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. ---, RECORDED PLAT		
5. PRIVATE CLAIMS ---		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19___ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19___ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E6: Maple post (not found)
 Y. Pine 24 S50W 11 " "
 Fir 10 N10E 7 " "
 No subsequent monuments found.

Corner 3: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E6: Re-established June 24, 1971 on line between section corners 39.977 chains to N and to S.

Corner 3: Established July 22, 1971 on line between section corner 19.988 chains N and 1/4 corner 19.988 chains S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner E6: Red Oak 8 N13°W (mag.) 22.1 ft. "1/4S, NBT"
Red Oak 8 S45°W (mag.) 37.2 ft. "1/4S, NBT"
Variation 1°00' East at this corner

Witnesses for Corner 3: Red Oak 8 N88°W (mag.) 12.7 ft. "1/16S, BT"
Red Oak 6 S83°E (mag.) 4.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ SEAL _____

FOR STATE AND UNITED STATES AGENCIES: _____

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 27, 1972**

CHIEF OF SURVEY PART
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**