

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	1. 42 N 32 XX W	G 4
2. PROPERTY CONTROLLING IN SECTION 10	1. 42 N 32 XX W	3
3. MISCELLANEOUS PROPERTY IN SECTION	N S R W	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were in a field survey on **see below** 19____ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 1 and 2 above were in a field survey on 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G 4: Yellow Pine post (not found)
Spruce Pine 10 S35E 13 (not found)
Y. Pine 12 N37W 13 " "
No subsequent monuments found

Corner 3: Not established in original survey, nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Corner G 4: Re-established June 23, 1971 on line between section corners 39.997 chains to N and to S.

Corner 3: Established June 23, 1971 on line between section corner 19.998 ch. N and 1/4 corner 19.998 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner G4: J. Pine 5 N60°E (mag.) 28.1 ft. "1/4S, NBT"
J. Pine 5 S25°E (mag.) 33.8 ft. "1/4S, NBT"

Witnesses for Corner 3: J. Pine 11 S17°E (mag.) 23.0 ft. "1/16S, BT"
J. Pine 13 S83°E (mag.) 35.3 ft. "1/16S, BT"

SIGNED BY _____

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SEAL _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

APPROVED AND SIGNED BY _____

DATE _____

November 27, 1972

SEAL _____

Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**

Form No. ML M736
 DOUBLEDAY BROS. & CO., PALM BEACH, FLA.

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS