

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	E. 42N ^N X R. 32 ^W	E 4
2. PROPERTY CONTROLLING IN SECTION		
3. MISCELLANEOUS PROPERTY IN SECTION		
4. LOT NO. ————, RECORDED PLAT		
5. PRIVATE CLAIMS ————		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on **June 23**, 19**71**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and, or subsequent restoration:

Yellow Pine post	(not found)
Y. Pine 8 S35W 22	" "
Spruce Pine 8 N35E 4	" "

No subsequent monuments found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner re-established on line between section corners 39.977 ch. to N. and to S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 4" aluminum cap.

J. Pine 7 S50°E (mag.) 25.3 ft. "1/4S, NBT"
J. Pine 7 N 9°W (mag.) 9.4 ft. "1/4S, NBT"

Variation 0°10' East at this corner.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE **November 27, 1972**

CHIEF OF SURVEY PARTY

 MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**