

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	REGISTER OF DEEDS STAMP AND FILING NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. <del>XX</del> R. 32 <del>XX</del> W.	F7	
2. PROPERTY CONTROLLING IN SECTION 16	T. 42 N. <del>XX</del> R. 32 <del>XX</del> W.	16	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.		
4. LOT NO. RECORDED PLAT			
5. PRIVATE CLAIMS			

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on **see below** 19... established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19... found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner F7: Yellow pine post (not found)**  
 Y. Pine 10 S31W 7 " "  
 Y. Pine 12 N75E 11 " "

**Found a 4"x4" squared wood post of some age, set by unknown party S5°15'E 1.635 ch. from corner as re-established here.**

**Corner 16: Not established in original survey. Found a scribed wood post, set by unknown party in a N&S fence line S42°E 21.9 ft. from corner as established here.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner F7: Neither physical evidence on the ground nor measurements to known corners in this township support the found wood post; therefore, on June 22, 1971, I re-established the corner on line between section corners 39.810 ch. to E and to W.**

**Corner 16: The found post was evidently supposed to be midway on line between found posts at 1/4 corner and section corner, and while nearly equidistant, is far north of being on a line between them. On May 8, 1972, I re-established this corner on line between new section corner 19.905 ch. E and new 1/4 corner 19.905 ch. W.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

**Witnesses for Corner F7: Red Oak 7 N 3°W (mag.) 15.9 ft. "1/4S, NBT"  
 Red Oak 8 S54°E (mag.) 18.8 ft. "1/4S, NBT"**

**Witnesses for Corner 16: J. Pine 10 S32°W (mag.) 44.9 ft. "1/16S, BT"  
 J. Pine 12 N73°W (mag.) 46.6 ft. "1/16S, BT"  
 Variation 1°00' East at this corner.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES: \_\_\_\_\_

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 27, 1972**

**Arthur O. Enger**

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**