

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 K.	F 9
2. PROPERTY CONTROL- ING IN SECTION- 28	T. 42 N. R. 32 K.	#1 & #2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F 9: White pine post (not found)
 Y. Pine 22 S21E 34 " "
 W. Pine 14 N15W 41 " "

Found a 3"x3" cedar post S28 1/2°E 81.0 ft. and a 3/4" I.D. iron pipe S25°W 73.9 ft. from corner reported here, presumably indicating confusion as to the true corner location.

Corner 1 & 2: Not established in original survey, nor, for Corner 1, subsequently, apparently. A fence corner bears S45°E 1.225 ch. from Corner 2 as reported here, indicating prior establishment by approximation.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F 9: Neither physical evidence on the ground nor measurements to known corners in this township support the found monuments; therefore, On June 28, 1971, I re-established the corner on line between section corners 39.907 ch. to E and to W.
Corner #1: Established May 4, 1972 on line between section corner 19.953 ch. W and 1/4 corner 19.953 ch. E.
Corner #2: Fence apparently originates from approx. corners to E and W. Therefore, established corner on August 19, 1971 on line between section corner 19.953 ch. E and 1/4 corner 19.953 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner F9: Red Oak 8 N10°W (mag.) 15.7 ft. "1/4S, NBT"
 Red Oak 10 S70°W (mag.) 6.3 ft. "1/4S, NBT"
Witnesses for Corner #1: W. Birch 6 N56°E (mag.) 10.6 ft. "1/16S, BT"
(Variation 0°20' East) W. Birch 6 S10°E (mag.) 12.9 ft. "1/16S, BT"
Witnesses for Corner #2: J. Pine 4 N22°E (mag.) 25.6 ft. "1/16S, BT"
(Variation 0°30' West) J. Pine 5 S74°E (mag.) 29.2 ft. "1/16S, BT"
 J. Pine 5 S52°W (mag.) 9.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **October 31, 1972**

Arthur O. Enger
 Michigan Registered Land Surveyor
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**