

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY-----	T. 42 N. R. 32 E.	G12	
2. PROPERTY CONTROLLING IN SECTION 34	T. 42 N. R. 32 E.	10	
3. MISCELLANEOUS PROPERTY IN SECTION-----	T.----- N. S. R.----- E. W.		
4. LOT NO.-----, RECORDED PLAT-----			
5. PRIVATE CLAIMS-----			

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G12: White pine post (not found)**

Y. Pine 10 S31E 18 " "  
Y. Pine 20 N70W 23 " "

No subsequent monuments found.

**Corner 10: Not established in original survey. Found a fence corner N36°E 1.150 ch. from corner reported here, for an approximate corner.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G12: Re-established August 2, 1971 on line between section corners 40.047 ch. to N and to S.**

**Corner 10: Established August 2, 1971 on line between 1/4 corner 20.024 ch. N and section corner 20.023 ch. S.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

**Witnesses for Corner G12: Red Oak 6 N69°E (mag.) 4.0 ft. "1/4S, NBT"**  
**(Variation 0°30' West) Red Oak 6 S20°E (mag.) 44.7 ft. "1/4S, NBT"**

**Witnesses for Corner 10: Red Oak 5 West (mag.) 22.0 ft. "1/16S, BT"**  
**(Variation 2°40' East) Red Oak 5 N47°E (mag.) 20.0 ft. "1/16S, BT"**

**Also squared and scribed a 6" red oak S78°E 1.3 ft. from Corner G12.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 30, 1972**

MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger** (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**