

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 W. <del>XX</del>	E 10	
2. PROPERTY CONTROLLING IN SECTION	29 T. 42 N. R. 32 W. <del>XX</del>	7 & 14	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.		
4. LOT NO. _____	RECORDED PLAT _____		
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19\_\_\_ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E 10:** Hemlock post (not found) No subsequent monuments found.  
 Hemlock 14 S45W 35 " "  
 W. Pine 12 N45E 21 " "

**Corners 7 and 14:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E 10:** Re-established August 19, 1971 on line between section corners 39.887 ch. to N and to S.

**Corner 7:** Established May 4, 1972 on line between section corner 19.944 ch. N and 1/4 corner 19.944 ch. S.

**Corner 14:** Established August 19, 1971 on line between 1/4 corner 19.944 ch. N and section corner 19.944 ch. S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner E10:** Aspen 7 S10<sup>0</sup>W (mag.) 20.4 ft. "1/4S, NBT"  
 (Variation 0<sup>0</sup>30' East) Aspen 6 S74<sup>0</sup>W (mag.) 7.0 ft. "1/4S, NBT"  
 Aspen 6 N74<sup>0</sup>E (mag.) 11.8 ft. "1/4S, NBT"

**Witnesses for Corner 7:** Aspen 8 N27<sup>0</sup>W (mag.) 85.3 ft. "1/16S, BT"  
 (Variation 0<sup>0</sup>00') J.Pine 6 S23<sup>1</sup>/<sub>4</sub><sup>0</sup>W (mag.) 75.7 ft. "1/16S, BT"

**Witnesses for Corner 14:** J. Pine 8 S11<sup>0</sup>W (mag.) 29.6 ft. "1/16S, BT"  
 (Variation 0<sup>0</sup>00') Aspen 6 N84<sup>0</sup>W (mag.) 39.1 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 28, 1972**

**Arthur O. Enger** (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**