

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 E.	I 12
2. PROPERTY CONTROLLING IN SECTION 34	T. 42 N. R. 32 E.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Eger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I 12:** Fir post (not found)  
 Spruce 6 S50W 18 " "  
 Fir 8 N37E 6 " "  
 No subsequent monuments found

**Corner 7:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I 12:** Re-established August 2, 1971 on line between section corners 40.101 ch. to N and to S.

**Corner 7:** Established August 2, 1971 on line between section corner 20.050 ch. N and 1/4 corner 20.051 ch. S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner I 12:** Tamarack 5 N28°E (mag.) 7.4 ft. "1/4S, NBT"  
 Tamarack 4 S46°E (mag.) 11.4 ft. "1/4S, NBT"  
 Tamarack 4 S50°W (mag.) 12.2 ft. "1/4S, NBT"

**Witnesses for Corner 7:** Tamarack 10 N11°E (mag.) 87.2 ft. "1/16S, BT"  
 W. Spruce 8 N25°W (mag.) 79.1 ft. "1/16S, BT"  
 (Variation 1°00' West)

Also squared and scribed a 5" choke cherry tree 2.2 links E. of pipe.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Eger DATE November 28, 1972  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Arthur O. Eger**  
**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581