

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 E.	E 12
2. PROPERTY CONTROLLING IN SECTION	32 T. 42 N. R. 32 E.	7 & 14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on **see below** 19__ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19__ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E12: Hemlock post (not found) No subsequent monuments found.
 Y. Pine 10 S81E 35 " "
 W. Pine 16 N56W 33 " "

Corners 7 & 14: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E12: Re-established September 1, 1971 on line between section corners 39.892 ch. to N and to S.
Corner 7: Established September 1, 1971 on line between section corner 19.946 ch. N and 1/4 corner 19.946 ch. S.
Corner 14: Established September 1, 1971 on line between section corner 19.946 ch. S and 1/4 corner 19.946 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 3/6" iron pipe with 4" aluminum cap.
Witnesses for Corner E12: Red Maple 5 N28°W (mag.) 28.6 ft. "1/4S, NBT"
(Variation 1°05' West) Red Oak 6 S67°E (mag.) 7.5 ft. "1/4S, NBT"
Witnesses for Corner 7: Red Pine 22 S 3°W (mag.) 85.4 ft. "1/16S, BT"
(Variation 0°45' West) W. Birch 12 N70°E (mag.) 62.2 ft. "1/16S, BT"
Witnesses for Corner 14: Cedar 8 S72°E (mag.) 36.7 ft. "1/16S, BT"
(Variation 0°30' West) Cedar 6 S18°E (mag.) 31.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES: _____

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 28, 1972**

Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**