

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. ^{N.} R. 32 W. ^{W.}	H 9
2. PROPERTY CONTROLLED BY ING IN SECTION	T. 42 N. ^{N.} R. 32 W. ^{W.}	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. ^{N.} R. W. ^{W.}	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19____ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3 and 4 above were, in a field survey on 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H 9: Yellow pine post (not found)
 Y. Pine 10 S71E 10 " "
 S. Pine 16 N36W 11 " "

Found a dead 6" aspen blazed on 4 sides N9°W 10 lks. and a 2" I.D. iron pipe with octoganal pipe union S14½°E 2.502 ch. from corner reported here.

Corner 2: Not established in original survey. Found a fence corner S88°E 44 ft. from corner reported here.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Corner H 9: No information on origin of found iron pipe, but it is grossly inconsistent with known corners in township and there is no physical evidence on the ground to support it. Therefore, on June 29, 1971, I re-established the corner proportionately on line between section corner 40.138 ch. W and section corner 40.148 ch. E, a point consistent with the blazed dead aspen.

Corner 2: No evidence as to precise origin of fence corner, as it is not even consistent with other fences in NE¼ of Sec. 27. Therefore, on July 22, 1971, I established the corner on line between 1/4 corner 20.074 ch. W and Section corner 20.074 ch.E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner H9: R. Pine 5 S54°W (mag.) 8.5 ft. "1/4S, NBT"
 R. Pine 4 N35°E (mag.) 27.2 ft. "1/4S, NBT"
 (Variation 2°00' West)

Witnesses for Corner 2: Red Maple 6 S26°E (mag.) 42.0 ft. "1/16S, BT"
 White Birch 11 S47°W (mag.) 30.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ SEAL _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE **November 28, 1972**

Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**