

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 W.	G 10
2. PROPERTY CONTROLLING IN SECTION 28	T. 42 N. R. 32 W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G 10: Yellow pine post (not found)**  
                   Y. Pine 10 S71E 10       "   "  
                   S. Pine 16 N36W 11       "   "  
**No subsequent monuments found.**

**Corner 7: Not established in original survey. Found a fence corner (S and W) bearing S56°E 85 links from corner reported here.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G10: Found a N&S fence line about 1 ch. E, but no corner and no evidence, physical or by measurement, to show that the fence is on the true section line; therefore, on June 29, 1971, I re-established the corner on line between section corners 39.951 ch. to N and to S.**

**Corner 7: Found no physical evidence on the ground nor measurements from known corners in the township to support the fence corner location; therefore, on May 5, 1972, I established the corner on line between section corner 19.976 ch. N and 1/4 corner 19.976 ch. S.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

**Witnesses for Corner G10: J. Pine 6 N52°W (mag.) 10.8 ft. "1/4S, NBT"**  
                                   J. Pine 5 S40°W (mag.) 8.1 ft. "1/4S, NBT"

**Witnesses for Corner 7: J. Pine 8 S28°W (mag.) 13.1 ft. "1/16S, BT"**  
                                   J. Pine 6 N74°W (mag.) 12.5 ft. "1/16S, BT"

**Variation 2°30'W at this corner.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 28, 1972**

MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**