

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 ^{N.} XX R. 32 ^{XX} W.	H11
2. PROPERTY CONTROLLING IN SECTION	T. 42 ^{N.} XX R. 32 ^{XX} W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ ^{N.} _____ XX R. _____ ^{XX} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H 11: Maple post (not found)
 Cedar 10 S53E 41 " "
 Maple 4 N 5W 11 " "
 Found a squared cedar post S84°E 1.095 ch. from corner reported here, as set by unknown party for an approximate corner.

Corner 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H 11: Re-established July 7, 1971 on line between section corners 40.144 ch. to E and to W.

Corner 2: Established August 2, 1971 on line between section corner 20.072 ch. E and 1/4 corner 20.072 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H 11: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Witnesses to Corner H11: Aspen 7 S70°W (mag.) 9.0 ft. "1/4S, NBT"
 Aspen 7 N17°E (mag.) 8.0 ft. "1/4S, NBT"
 (Variation 1°05' West) R. Pine 16 S37°E (mag.) 41.0 ft. "1/4S, NBT"

Corner 2: 4"x4"x6' squared and scribed W. Pine post
 Witnesses to Corner 2: W. Pine 18 S21°W (mag.) 21.1 ft. "1/16S, BT"
 W. Pine 14 N27°W (mag.) 25.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 28, 1972
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581