

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 42 N. R. 32 E. W.	D 5	
2. PROPERTY CONTROLLING IN SECTION 17	T. 42 N. R. 32 E. W.	2	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner D5: Hemlock post (not found)**  
 Hemlock 10 S46W 36 " "  
 Hemlock 8 N50E 30 " "  
 No subsequent monuments found.

**Corner 2: Not established in original survey nor subsequently, apparently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner D 5: Re-established July 23, 1971 on line between section corners 40.006 ch. to E and to W.**

**Corner 2: Established July 23, 1971 on line between section corner 20.003 ch. E and 1/4 corner 20.003 ch. W.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

**Witnesses for Corner D5: Red Maple 6 N13°E (mag.) 25.4 ft. "1/4S, NBT"**  
**W. Pine 22 S86°W (mag.) 48.5 ft. "1/4S, NBT"**  
**Variation 1°30' West at this corner.**

**Witnesses for Corner 2: Red Oak 8 S74°E (mag.) 17.8 ft. "1/16S, BT"**  
**Red Oak 7 N28°E (mag.) 32.6 ft. "1/16S, BT"**  
**Variation 1°50' West at this corner.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **November 27, 1972**

MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger** (SEAL)

**Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**