

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 42N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 23 and 26

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 5, 1972

WITNESSES TO CORNER..... J. Pine 5 S21°W (mag.) 21.4 ft. "1/4S, NBT"



J. Pine 4 N34½°E (mag.) 31.9 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a rotted-off 3"x3" squared wood post lying on ground at a fence corner N41°E .705 ch. from corner.

Checked direction and distance from found wood post to the section corners to E and W and found it not to be reasonably consistent with them. Therefore, re-established corner on line between section corners 40.038 ch. to E and to W.

Variation 0°15' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE June 23, 1972