


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY  
T 42N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 25 and 26  
CORNER MONUMENT Wisconsin-Michigan Power Company concrete tetrahedron with brass cap.  
DATE MONUMENT PLACED AND WITNESSED May 5, 1972  
WITNESSES TO CORNER..... J. Pine 7 S68°W (mag.) 49.2 ft. "1/4S, NBT"



Red Oak 7 N12½°E (mag.) 21.7 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a concrete tetrahedron with square brass identification plate as set by personnel of Wisconsin-Michigan Power Company.

Wisconsin-Michigan Power Company records indicate monument placed from an original BT. I examined the corner area on the above date and found a burned jack pine stump corresponding to an original Spruce Pine 4 S51W 58 in proper position from monument, with a charred blaze and axe notch facing the corner. Markings appear as having been made in the manner of the original method of marking, therefore accepted the monument as marking the original corner location.

Variation 1°00' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION: SIGNED Arthur O. Enger DATE June 23, 1972  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

Forestry Division, Lansing

Area Forester

District Surveyor