

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 23, 24, 25, and 26

CORNER MONUMENT Wisconsin-Michigan Power Company concrete tetrahedron with
brass cap.

DATE MONUMENT PLACED AND WITNESSED May 5, 1972

WITNESSES TO CORNER..... W. Pine 10 S65°W (mag.) 60.0 ft. "S26, NBT"



W. Pine 8 N26½°E (mag.) 59.0 ft. "S24, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a concrete tetrahedron with square brass identification plate as set by personnel of Wisconsin-Michigan Power Company.

Wisconsin-Michigan Power Company records indicate monument placed from two probable original BT's. I examined the corner area on the above date and found two pine stumps in proper position, corresponding to the original BT's in species, relative and absolute size, distance and bearing, therefore accept monument as marking the original corner location. No marks on stumps, which are in poor condition.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 23, 1972