

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 22 and 23

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 9, 1972

WITNESSES TO CORNER..... Cedar 7 N64°E (mag.) 27.1 ft. "1/4S, NBT"



Cedar 6 S38°W (mag.) 39.2 ft. "1/4S, NBT"

Also squared and scribed a 5" cedar N67°W 4½ links
from corner.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found the rotted remnants of a cedar post lying on ground N85°E 28 links from corner, from which a cedar stump with blaze scribed "BT" bears N43½°W 19½ links, but could not find point of post in ground. Person who marked the cedar stump is unknown. The found wood post appears to have no support by measurements or other physical evidence in the vicinity, therefore, I re-established the corner on line between section corners 40.101 ch. to N and to S. On re-established section line going N from this corner, at 5.63 ch. I found a W. Pine stump corresponding in size and position with an original line tree, originally reported as being 5.66 ch. N of 1/4 corner. I believe the corner position as re-established herein to be duly supported by the evidence, but the found post not to be so supported.

Variation 0°45' West at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 18, 1972