

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 14, 15, 22, and 23

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 9, 1972

WITNESSES TO CORNER..... B. Spruce 6 N 5°W (mag.) 34.0 ft. "S15, NBT"



Red Maple 5 S78°E (mag.) 23.7 ft. "S23, NBT"

Red Maple 6 S30°W (mag.) 13.5 ft. "S22, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1" I.D. x 37" iron pipe in place, as set by unknown surveyor many years ago. The found pipe was apparently set from the original BT's. WMPCo. records indicate the presence of BT's, presumably identifiable, in the 1940's. Examination of the corner area on 5/9/72 revealed the presence of stump to the NW and a down tree to the SE, corresponding in species, relative and absolute size, distance, and bearing to the original BT's; but with no marks other than a possible burned axe blaze on the tree to the SE. As the evidence seems conclusive, I accepted the found pipe as marking the original corner location.

Variation 0°00' at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 18, 1972