

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER East 1/16 corner between Sections 5 and 8

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 30, 1971

WITNESSES TO CORNER..... J. Pine 6 S52°E (mag.) 47.2 ft. "1/16S, BT"



J. Pine 10 S11°E (mag.) 50.1 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner not established in original survey nor subsequently, apparently.

Corner established on August 30, 1971 by proportionate measurement on line between section corners 19.978 ch. E and 59.944 ch. W. (1/4 corner falls in a pond.)

Variation 1°15' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE October 31, 1972