


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 9 and 16
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 21, 1971
WITNESSES TO CORNER..... J. Pine 6 S3 $\frac{1}{2}$ ^oE (mag.) 36.1 ft. "1/4S, NBT"



J. Pine 6 S50^oW (mag.) 29.3 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1 $\frac{1}{2}$ " I.D. iron pipe N76^oE .253 chains and a 3/4" I.D. iron pipe S51^oW .742 chains, set by unknown parties, and presumed by me to be indicative of confusion as to true location of corner.

Corner re-established on June 21, 1971 on line between section corners 39.816 chains to E and to W.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE October 30, 1972