

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 42N R 32W

DESCRIPTION OF CORNER East 1/16 corner between Sections 9 and 16

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 25, 1971

WITNESSES TO CORNER..... J. Pine 3 S29°E (mag.) 11.3 ft. "1/16S, BT"



J. Pine 2 S15°W (mag.) 21.8 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner not established in original survey nor subsequently, apparently.

Corner established on line between section corner 19.908 ch. E and 1/4 corner 19.908 ch. W.

Variation 0°10' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE October 30, 1972