

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 16, 17, 20, and 21

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 9, 1971

WITNESSES TO CORNER..... Red Oak 6 S32°W (mag.) 10.4 ft. "S20, NBT"



Red Oak 7 N58°W (mag.) 12.8 ft. "S17, NBT"

Red Oak 7 N1°E (mag.) 17.7 ft. "S16, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 4"x4" squared wood post lying on ground S12°E 1.25 ch., for an approximate corner. Corner placed proportionately on line between section corners 79.62 chains to E and to W, in accordance with method of original establishment. This placement puts the corner nearly on line between monuments at sec. cor. 4, 5, 32, & 33, T41-42N, R32W and sec. cor. 4, 5, 32, & 33, T42-43N, R32W, as would be expected by the method of original establishment. It is possible that uneven distances to sec. corners E & W of this one may have originally been the case, up to a magnitude of about 20 links; but it is difficult to determine what they were. Thus proportionate measurement was used.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE September 29, 1972
REGISTERED LAND SURVEYOR
Arthur O. Enger

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor