

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 3, 4, 9, and 10

CORNER MONUMENT 2½" O.D. x 42" iron pipe with brass cap. (by WMP Co.)

DATE MONUMENT PLACED AND WITNESSED June 9, 1971

WITNESSES TO CORNER..... J. Pine 6 N39°E (mag.) 12.1 ft. "S 3, NBT"



J. Pine 5 S48°E (mag.) 17.7 ft. "S10, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2½" O.D. x 42" iron pipe with brass cap set by employees of Wisconsin-Michigan Power Company. This corner checked by measuring to known corners in the township and was found to agree to within about 5 feet of its position as probably established at the time of the original government survey. In view of these facts, it appears acceptable as the true corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1972