

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 20, 21, 28, and 29

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 14, 1971

WITNESSES TO CORNER..... Red Maple 5 N31°E (mag.) 19.6 ft. "S21, NBT"



White Spruce 3 N50°W (mag.) 21.6 ft. "S20, NBT"

Aspen 7 S25°W (mag.) 10.6 ft. "S29, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by double proportionate measurements from corners 1 mile N, 1 mile S, 2 miles E, and 1 mile W. Proportioned distances from known corners to E and W and from known corners to N and S arrive at points only 22.4 links (14.8 ft.) apart, tending to indicate that the corner probably was set no further away than that from this point originally, which in view of the extensive loss of corners in this township, seems acceptable to the undersigned.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE September 28, 1972