

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 21, 22, 27, and 28

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 14, 1971

WITNESSES TO CORNER..... J. Pine 6 S54°W (mag.) 25.4 ft. "S28, NBT"



J. Pine 6 S19°E (mag.) 36.8 ft. "S27, NBT"

Aspen 8 N35°W (mag.) 7.0 ft. "S21, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found an iron pipe with old scribed post S52°15'E 1.112 ch. from corner, set by unknown party from unknown evidence. Corner re-established by single proportionate measurement on line between section corners 1 mile N and 2 miles S, in accordance with original method of subdivision. Double proportion not used because of indications that corner 1 mile north was originally established by mistake about 1/2 chain westerly of its reported position. However, even if double proportion were used, the corner would fall only 26 links (17.2 ft.) E of position established here. The found pipe appears unacceptable because of gross misalignment with surrounding known corners, a misalignment for which I could uncover no likely evidence of having occurred in the original survey.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1972

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor