

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 32W

DESCRIPTION OF CORNER Section Corner 27, 28, 33, and 34

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 15, 1971

WITNESSES TO CORNER..... Aspen 10 S70°E (mag.) 95.6 ft. "S34, NBT"



Aspen 7 N26°E (mag.) 49.1 ft. "S27, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1½" I.D. x 6' iron pipe at approximate corner location, set by unknown party. As the found iron pipe falls only 6.4 ft. from the calculated proportionate corner position, it was accepted as reasonably representing the true original corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 28, 1972