


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 41-42N R R 32 W

DESCRIPTION OF CORNER Section Corner common to Sections 4, 5, 32, & 33
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED September 4, 1968
WITNESSES TO CORNER..... Red Oak 10 S58W 56½ lks. "S5 NBT"



Red Oak 6 N64W 41½ lks. "S32 NBT"

Bigtooth Aspen 8 N39E 16 lks. "S33 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner established at record distances from a lake shore 5.00 ch. West, a stream crossing 12.87 ch. North, and the foot of a hill 5.00 ch. South. This position also agrees with a field note entry "Descend hill from post," going south from corner. Some pine stumps in vicinity, but none match the original BT's for relative position.

This corner was subsequently found to bear N89° 43'W 160.10 chains from a corner on the township line also reportedly set from ties to stream crossings. Record distance between corners was 160.00 chains. It is considered that the position re-established here is duly supported by measurements and calls to natural features.

An L.E.S. post marked "4, 5, 32, 33 APP." bears S24W 64 links. This post was obviously not intended to be at the true corner position, unless by coincidence.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/14/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68