


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 41-42 N R 32 W

DESCRIPTION OF CORNER Section Corner common to Sections 2, 3, 34 & 35
CORNER MONUMENT 3" x 3" brass cap in concrete tetrahedron
DATE MONUMENT ~~PLACED AND~~ WITNESSED September 10, 1968
WITNESSES TO CORNER..... Black Spruce 5 S67E 109½ lks. "S2 NBT"



Black Spruce 5 N79E 160 lks. "S35 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-witnessed monument as placed by Wisconsin Michigan Power Company, surveyors many years ago. Corner reportedly set by ties to stream crossings to north and west.

This corner was found to be S89°43'E 160.10 chains from a corner on the township line which was established from ties to a lake shore, stream crossing, and ridges. (Bearing by solar observation). As the record distance between these corners was 160.00 chains, it is considered that this monument is duly supported by measurements and ties to natural features.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

2/14/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68