


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 42 N R 32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 8
CORNER MONUMENT 1" I.D. x 36" galvanized iron pipe with 4" aluminum description cap
DATE MONUMENT PLACED AND WITNESSED May 20, 1970
WITNESSES TO CORNER..... Red Oak 13 N30°W 23.4 feet (horizontal distance) "1/4S, NBT"



Red Oak 13 N27°E 21.1 feet (horizontal distance) "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed midway on line between a known original section corner 39.96 chains S and a probable original section corner 39.96 chains N. Found no positive evidence of original post or its accessories, but while digging a hole for the new monument, found rotted scraps of wood set vertically into the soil, which could have been part of an old post. Position agrees with record call to a small brook reported as 1.70 chains N of the corner originally, but road construction has altered the course of the stream at this point. An old fence and field corner lies S35°W 87 links, but seems to be too far misplaced between section corners to be the original corner position.

SURVEYOR'S SEAL

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE April 29, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68